

**Specification No. :****Scope of Supply / Work :** Providing of double earthing to the 3Nos 160MVA PTR neutrals at 220KV GIS Erragadda.**Schedule of Material Quantities and Prices (PR No.1200008259)**

(All Financial Figures in Rs.)

ERP Item No.	Schd. No.	Material Code	Material Description	HSN Code	Qty.	Unit	Total price/Unit	GST Rate(%)	GST/ Unit	Total Landed Cost /Unit	Total Amount Excl. GST	Total Amount Incl. GST
1		40000447	100 X 16 MM GI EARTH FLAT	72111450	30	M	990.37	18%	178.27	1,168.64	29,711.10	35,059.20

NOTE: CGST and SGST amounts shall be shown in separate columns in the vendor invoices

Total 29,711.10 35,059.20

**Schedule of Service Quantities and Prices (PR No.1200008259)**

(All Financial Figures in Rs.)

ERP Item No./ Sub-Item No.	Schd No.	Service Code	Service Description	HSN Code	Qty.	Unit	Rate/Unit	Per	Total Base Value	GST (%)	Total GST	Total Tax Portion	Total Amount
2			estimate towards providing of double eart										
2 /1		CS16-16A	Laying of earth mat including Excavation of trenches, welding, connecting to equipment and connecting lightning shield to earth mat and earthing of fence posts, drilling and connecting earth rods including connecting cast iron pipes as per Drg. No.SET(P)/149/82 with the following sizes of MS Flats / GI Flats.(for 220kV and 132kV) including fabrication. 220 and 132kV 100x16mm MS Flat / GI Flat.	995429	30	RMT	113.00	1	3,390.00	18%	610.20	610.20	4,000.20

NOTE: CGST and SGST amounts shall be shown in separate columns in the vendor invoices

Total 3,390.00 4,000.20

Grand Total: 39,059.40

Amount in words : Thirty Nine Thousand Fifty Nine Rupees Forty Paise

