

Specification No. : W- /25-26

Scope of Supply / Work : Painting of MS Structures on 33 KV side at 132/33 KV SS Nalgonda with one coat of red oxide & two coats of aluminium paint including material and labour charges.

Schedule of Service Quantities and Prices (PR No.1200008807)

(All Financial Figures in Rs.)

| ERP Item No./ Sub-Item No. | Schd No. | Service Code | Service Description | HSN Code | Qty. | Unit | Rate/Unit | Per | Total Base Value | GST (%) | Total GST | Total Tax Portion | Total Amount |
|---------------------------------|----------|--------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|------|-----------|-----|------------------|---------|-----------|-------------------|--------------|
| 1 | 1 | | 33 KV Structure painting at NLG SS. | | | | | | | | | | |
| 1 / 1 | 1 | OM7-B | One coat of 1st Grade Red Oxide Paint including labour charges for scratching and cleaning of towers including cost of paint, brushes etc. | 995429 | 34.4 | MT | 2,780.00 | 1 | 95,632.00 | 18% | 17,213.76 | 17,213.76 | 112,845.76 |
| 1 / 2 | 1 | OM3-A | Painting of towers with two coats of aluminum paint using Aluminum paint 1st grade containing 306 Kg of Aluminum paste for 18 liters of thinner 1st coat is to be applied before erection of towers and 2nd coat after stringing and half round welding, first coat of 1st grade paint duly scratching and cleaning of towers, including labour charges, cost of paint, brushes etc., | 995429 | 34.4 | MT | 5,650.00 | 1 | 194,360.00 | 18% | 34,984.80 | 34,984.80 | 229,344.80 |
| 1 / 3 | 1 | OM5-C | Painting of towers with two coats of aluminum paint using Aluminum paint 1st grade containing 306 Kg of Aluminum paste for 18 liters of thinner 1st coat is to be applied before erection of towers and 2nd coat after stringing and half round welding. Second coat of 1st grade Aluminum paint duly scratching and cleaning of towers, including labour charges, cost of paint, brushes etc. | 995473 | 34.4 | MT | 3,460.00 | 1 | 119,024.00 | 18% | 21,424.32 | 21,424.32 | 140,448.32 |
| Sub-Total of Schd. No.1: | | | | | | | | | | | | 482,638.88 | |

NOTE: CGST and SGST amounts shall be shown in separate columns in the vendor invoices

Total 409,016.00

482,638.88

Amount in words : Four Lakh Eighty Two Thousand Six Hundred Thirty Eight Rupees Eighty Eight Paise

