

Specification No. :

Scope of Supply / Work : Re-stringing of existing 220KV Narketpally-Suryapet & Narketpally-Huzurnagar DC line from loc no 289(B+0) to 298 (C+0) in OMC Nalgonda

Schedule of Service Quantities and Prices (PR No.1200008804)

(All Financial Figures in Rs.)

| ERP Item No./ Sub-Item No. | Schd No. | Service Code | Service Description | HSN Code | Qty. | Unit | Rate/Unit | Per | Total Base Value | GST (%) | Total GST | Total Tax Portion | Total Amount |
|----------------------------|----------|--------------|---|----------|------|------|------------|-----|------------------|---------|-----------|-------------------|--------------|
| 1 | | | Name of the work: The estimate envisage | | | | | | | | | | |
| 1 / 1 | | OM33-H | RE-STRINGING OF POWER CONDUCTOR ON THE EXISTING LINES (FOR CORRECTION OF SAG) INCLUDING FIXING OF TENSION INSULATORS / SUSPENSION INSULATORS, HARDWARE AND ACCESSORIES, ROUGH SAGGING, JOINTING, TENSIONING, CLIPPING AND FIXING OF PERFORMED ARMOUR RODS AND VIBRATION DAMPERS, MEASURING GROUND CLEARANCES WHEREVER NECESSARY. WHICH INCLUDES THE WORKS INVOLVED IN THE CROSSING OF LT, 11 KV & 33 KV POWER LINES VIZ DISMANTLING AND RESTRINGING OF CONDUCTOR. 220 & 132KV 6. NOS. MOOSE CONDUCTORS | 995429 | 3.03 | KM | 160,352.50 | 1 | 485,868.08 | 18% | 87,456.25 | 87,456.25 | 573,324.33 |

NOTE: CGST and SGST amounts shall be shown in separate columns in the vendor invoices

Total 485,868.08

573,324.33

Amount in words : Five Lakh Seventy Three Thousand Three Hundred Twenty Four Rupees Thirty Three Paise

History of Submit/Forward Note :

SEOMC02NLG 16.03.2026 17:44:18
Submitted for approval
DEONM01NLG 09.03.2026 17:17:08
FORWARDED FOR APPROVAL
DEONM02NLG 09.03.2026 16:42:35
submitted and forwarded to DE?O&M/Nalgonda
DEONM02NLG 09.03.2026 16:39:20
submitted



DEONM03NLG 09.03.2026 16:35:57

Re-stringing of existing 220KV Narketpally-Suryapet &
Narketpally-Huzurnagar DC line from loc no 289(B+0) to 298 (C+0) in Nal
gonda lines Subdivision.

DEONM03NLG 09.03.2026 16:34:08

Re-stringing of existing 220KV Narketpally-Suryapet &
Narketpally-Huzurnagar DC line from loc no 289(B+0) to 298 (C+0) in Na
lgonda lines Subdivision.



This document is generated from TGTRANSCO's ERP system